



Calling Bullshit

The Art of Skepticism in a Data-Driven World





Jevin West
Information School
University of Washington



jevinw@uw.edu
@jevinwest, @callin_bull

Fermilab Arts and Lecture Series, April 9, 2021





Mapping Disinformation Spread across Online Communities

Research





Image: Kate Starbird

We are **inundated** with information...





The consequences are profound.



Photo: Carl Bergstrom




And people don't know who to trust.

The point of modern propaganda isn't only to misinform or push an agenda. It is to exhaust your critical thinking, to annihilate truth."

— Garry Kasparov (2016)







Erik Hinton
@erikhinton

...

This totally real Amazon employee has a totally real profile image and is not at all a GAN composite.



Lulu at CMH1 
@AmazonFCLulu

...



I'm beginning to worry that there's a problem with UTIs across the country, given how frequently many of you need a bathroom break?

You really should see doctors about that.


Which you can do if you work full time at an Amazon FC, since we get comprehensive health benefits!

3:24 PM · Mar 29, 2021 · Twitter Web App





whichfaceisreal.com



The COVID pandemic
upended all of our lives.





Even in science.


Photo: Carl Bergstrom

We began with scientific uncertainty
about a virus that was never *in* humans before December 2019.



Into this
uncertainty
vacuum
flow...

Meta-analysis of infection fatality rates of COVID-19 by month of study publication





...s cellphone while securing the entrance of a nearly empty shop.
(SFOURI/AFP via Getty Images)


...n Fewer Cellphone Us ...ay Suggest a High CCI ...oll

22, 2020 Updated: April 2, 2020

Organized disinformation campaigns

...ne that reports are emerging m
...reporting actual numbers of a
...[CoronavirusOutbreak](#). Increas
...pouring areas of Wuhan indica
...being cremated silently.

...de



...er for Android

Abstract:

We are currently witnessing a major epidemic caused by the 2019 novel coronavirus (2019-nCoV). The evolution of 2019-nCoV remains elusive. We found 4 insertions in the spike glycoprotein (S) which are unique to the 2019-nCoV and are not present in other coronaviruses. Importantly, amino acid residues in all the 4 inserts have identity or similarity to those in the HIV-1 gp120 or HIV-1 Gag. Interestingly, despite the inserts being discontinuous on the primary amino acid sequence, 3D-modelling of the 2019-nCoV suggests that they converge to constitute the receptor binding site. The finding of 4 unique inserts in the 2019-nCoV, all of which have identity /similarity to amino acid residues in key structural proteins of HIV-1 is unlikely to be fortuitous in nature. This work provides yet unknown insights on 2019-nCoV and sheds light on the evolution and pathogenicity of this virus with important implications for diagnosis of this virus.

Introduction

Coronaviruses (CoV) are single-stranded positive-sense RNA viruses that infect animals and humans. These are classified into 4 genera based on their host specificity: *Alphacoronavirus*, *Betacoronavirus*, *Deltacoronavirus* and *Gammacoronavirus* (Snijder et al., 2006). There are seven known types of CoVs that includes 229E and NL63 (Genus Alphacoronavirus), OC43, HKU1, MERS and SARS (Genus Betacoronavirus). While 229E, NL63, OC43, and HKU1 commonly infect humans, the SARS and MERS outbreak in 2002 and 2012 respectively occurred when the virus crossed-over from animals to humans causing significant mortality (J. Chan et al., n.d.; J. F.

2019, December 2019, another outbreak of

Uncanny similarity of unique inserts in the 2019-nCoV protein to HIV-1 gp120 and Gag

Overview of attention for article published in bioRxiv



99 news outlets
23 blogs
1 policy source

17034 tweeters
22 Facebook pages
11 video uploaders

32 Dimensions

Dreadful preprints

Effect of millimeter waves on the growth and induction of coronavirus in skin cells

Behri¹, M.G. Rocca¹, M. Jafferany², O. Yu.
K.M. Lomonosov³ and T. Lotti^{1,3}

¹Department of Nuclear and Radiation Physics, G. Marconi University, Bologna, Italy; ²Department of Dermatology, Michigan State University, Michigan, USA; ³Department of Dermatology, Moscow State Medical University, Moscow, Russia

Received May 13, 2020 – Accepted June 9, 2020

Millimeter waves could be absorbed by dermal cells and play the main role in producing Coronavirus. Electrons and atoms and has an inductor-like structure and round inductors. Inductors interact with external waves within the cells. The shapes of these waves are based on the bases of their DNA source. These waves produce holes, some extra hexagonal and pentagonal structures and form virus-like structures such as Coronavirus. It is necessary that the wavelength of external waves be suitable for the cells could be good candidates for applying in the treatment of COVID-19) within cells.

Equally dreadful peer- reviewed work

Hydroxychloroquine or chloroquine with or without a macrolide for treatment of COVID-19: a multinational registry analysis

Amal S Desai, Frank Ruschitzka, Amit N Patel

Hydroxychloroquine or chloroquine, often in combination with a second-generation macrolide, have been proposed for the treatment of COVID-19, despite no conclusive evidence of their benefit. Although general contraindications such as autoimmune disease or malaria, the safety and benefit of these drugs have not been evaluated in COVID-19.

We conducted a multinational registry analysis of the use of hydroxychloroquine or chloroquine with or without a macrolide for the treatment of COVID-19. The registry comprised data from 671 hospitals in six continents. Between Dec 20, 2019, and April 14, 2020, with a positive laboratory finding for SARS-CoV-2, 10 698 patients were included in one of the treatments of interest within 48 h of diagnosis were included in one of four treatment groups: hydroxychloroquine alone, chloroquine with a macrolide, hydroxychloroquine with a macrolide, or hydroxychloroquine alone. Patients who received none of these treatments formed the control group. Patients for whom treatment was initiated more than 48 h after diagnosis or while they were on mechanical ventilation, or who had received remdesivir, were excluded. The main outcomes of interest were in-hospital mortality and the occurrence of de-novo ventricular arrhythmias (non-sustained or sustained ventricular tachycardia).

The study included 10 698 patients (mean age 53·8 years, 46·3% women) with COVID-19 were hospitalised during the study period. Of these, 14 888 patients were in the treatment groups (18 888 received chloroquine with a macrolide, 3016 received hydroxychloroquine, and 6204 received chloroquine with a macrolide) and 81 144 patients were in the control group. 10 698 (11·1%) patients were included in the analysis after adjusting for multiple confounding factors (age, sex, race or ethnicity, body-mass index, comorbidities, and its risk factors, diabetes, underlying lung disease, smoking, immunosuppression, and severity), when compared with mortality in the control group (9·3%), hydroxychloroquine with a macrolide (23·8%; 1·447, 1·35, 95% CI 1·223–1·457), hydroxychloroquine with a macrolide (23·8%; 1·447, 1·35, 95% CI 1·223–1·457), and chloroquine with a macrolide (22·2%; 1·368, 1·273–1·465), and chloroquine with a macrolide (22·2%; 1·368, 1·273–1·465) with an increased risk of in-hospital mortality. Compared with the control group, hydroxychloroquine with a macrolide (8·1%; 5·106, 4·2·369, 1·935–2·900), hydroxychloroquine with a macrolide (8·1%; 5·106, 4·2·369, 1·935–2·900), and chloroquine with a macrolide (6·5%; 4·011, 3·344–4·760) had an increased risk of de-novo ventricular arrhythmia during hospitalisation.

Conclusion: We did not confirm a benefit of hydroxychloroquine or chloroquine, when used alone or in combination with a macrolide, for COVID-19. Each of these drug regimens was associated with an increased frequency of ventricular arrhythmias when used for treatment of COVID-19.


† Chair in Advanced Cardiovascular Medicine at Brigham and Women's Hospital

Fake studies & astroturfing

Early treatment with hydroxychloroquine: a country-randomized controlled trial

Covid Analysis, August 5, 2020 (updated August 6, 2020)

@CovidAnalysis [Share](#) [Tweet](#)



any countries either adopted or declined early treatment with HCQ, forming a large country-randomized controlled trial. 2.0 billion people were assigned to the treatment group, and 663 million to the control group. As of August 6, 2020, an average of 38.5/million in the treatment group have died, and 440.2/million in the control group, relative risk 0.087. After adjustments, treatment and control deaths become 79.6/million and 630.0/million, relative risk 0.13. Confounding factors affect this estimate, including varying degrees of spread between countries. Accounting for predicted changes in spread, we estimate a relative risk of 0.21. **The treatment group has 79.1% lower chance of death.** We examined diabetes, obesity, hypertension, life expectancy, population density, urbanization, testing level, and intervention level, which do not account for the effect observed.

PANDA
PANDemics - DATA & ANALYTICS

ABOUT ▾ LIVE DATA MEDIA ▾ ANALYSIS STORIES ▾ CONTACT US

DONATE

SUBSCRIBE

Covid 19
Pandemic - Data
& Science that will
save lives and
livelihoods.

PANDA's analysis of the human
& economic cost of lockdowns.

COVID-19 LIVE FEED DATA

**Pandemics ~ Data & Analytics
(PANDA)**

Our mission is simple. We see in lockdown and its related
intrusions on civil liberties a serious threat not only to lives but to
civilization itself. This threat must be resisted.

Our view is that at this juncture, the science is quite clear on what
key policy responses should be—or should have been. But this is
no longer about the science, if it ever was. What is required now is
a mobilisation against what is essentially an enormous public
relations machine that is fuelling fear and removing agency from
people's lives the world over.

LATEST NEWS


Would You Jump?
Jan 26, 2021
Written by: Kerry Gorton Evans If
someone told you to jump off a bridge
would you do it? If they...

Bridging The Divide
Jan 26, 2021
Written by: Emma McArthur Whatever
we think about lockdowns, one thing
is clear. None of us want...

**PANDA Responds to Updated South
African Government Mask
Mandates**

f t in

Organized agnotogenesis





ABC News

@ABC

NEW: People who have been infected with COVID-19 and recovered are protected for up to three months and can safely interact with others, according to new CDC guidance.



Coronavirus updates: CDC forecast predicts death toll could reach 1 million by June. The United States has at least 167,242 deaths.

abcnews.go.com

Sloppy
reporting




IMAGE: ANSYS

The Viral 'Study' About Runners Spreading Coronavirus Is Not Actually a Study. *Vice News*

People who see
a crisis as a
career opportunity.

TECHNOLOGY

How to Misinform Yourself About the Coronavirus

Even if you avoid the conspiracy theories, tweeting through a global emergency is messy, context-free, and disorienting.

ALEXIS C. MADRIGAL JANUARY 28, 2020



CARLOS GARCIA RAWLINS / REUTERS

UNREPORTED TRUTHS ABOUT COVID-19 AND LOCKDOWNS

Part 1: Introduction and
Death Counts and Estimates

Cherry-picked anecdotes and studies



Numbers appear to carry authority.



They almost seem to carry



divine authority.

Photo: Carl Bergstrom



What can we do about it?

Media Literacy





Opinion

I Used to Think the Remedy for Bad Speech Was More Speech. Not Anymore.

How kids, lawsuits and legislation can save democracy.





CENTER FOR AN INFORMED PUBLIC


UNIVERSITY *of* WASHINGTON

Mission: resist strategic misinformation, promote an informed society, and strengthen democratic discourse.





The world is awash in bullshit. Politicians are unconstrained by facts. Science is conducted by press release. Higher education rewards bullshit over analytic thought. Startup culture elevates bullshit to high art. Advertisers wink conspiratorially and invite us to join them in seeing through all the bullshit — and take advantage of our lowered guard to bombard us with bullshit of the second order. The majority of administrative activity, whether in private business or the public sphere, seems to be little more than a sophisticated exercise in the combinatorial reassembly of bullshit.

<http://callingbullshit.org>



Penguin
Random
House





Even when you don't know how an algorithm or statistical test works, you can spot bullshit by looking carefully at what goes in and what comes out.

Mis/Disinformation

Correlation & causation

Selection bias

Pope Francis Shocks World, Endorses Donald Trump for President, Releases Statement



© 11/01/2016 Fabrica Tedzori Global, Politics 0




VATICAN CITY – News outlets around the world are reporting on the News that Pope Francis has made the unprecedented decision to endorse a US presidential candidate. His statement in support of Donald Trump was released from the Vatican this evening:

"I have been hesitant to offer any kind of support for either candidate in the US presidential election but I now feel that to not voice my concern would be a


dereliction of my duty as the Holy See. A strong and free **America** 🇺🇸 is vitally important in maintaining a strong and free world and in that sense what happens in American elections affects us all. The Rule of **Law** is the backbone of the American government as it is in any nation that strives for freedom and I now fear that the Rule of **Law** in America has been dealt a dangerous blow. The FBI, in refusing to recommend **prosecution** 🚔 after admitting that the law had been broken on multiple occasions by Secretary Clinton, has exposed itself as corrupted by political forces that have become far too powerful.



Data visualization



Big data / ML



Nature of science

Journal view

[illegible]

ROYAL SOCIETY OPEN SCIENCE

 Open Access

 Check for updates

 View PDF

 Tools  Share

Cite this article ▾


Section

Abstract

1. Introduction
2. Material and methods
3. Results
4. Discussion
5. Conclusion

Research articles

Susceptibility to misinformation about COVID-19 around the world

Jon Roozenbeek, Claudia R. Schneider, Sarah Dryhurst, John Kerr, Alexandra L. J. Freeman, Gabriel Recchia, Anne Marthe van der Bles and Sander van der Linden 

Published: 14 October 2020 | <https://doi.org/10.1098/rsos.201199>

 Review history

Abstract

Misinformation about COVID-19 is a major threat to public health. Using five national samples from the UK ($n=1050$ and $n=1150$), Ireland ($n=700$), the USA ($n=700$), Spain ($n=700$) and Mexico ($n=700$), we examine predictors of belief in the most common statements about the virus that contain misinformation. We also investigate the prevalence of belief in COVID-19 misinformation across different countries and the role of belief in such misinformation in predicting relevant health behaviours. We find that while public belief in misinformation about COVID-19 is not particularly common, a substantial proportion views this type of misinformation as highly reliable in each country

 Details

 References

 Related

 Figures

This Issue



October 2020

Volume 7, Issue 10

Article Information

Published by: [Royal Society](#)

Online ISSN: [2054-5703](#)

History:

Old School BS

New School BS

“Our collective mission is to refunctionalize customer-driven solutions for leveraging underutilized portfolio opportunities.”

New School BS

“Our collective mission is to refunctionalize customer-driven solutions for leveraging underutilized portfolio opportunities.”

“While short of statistical significance after Bonferroni correction ($p=0.13$), our results underscore a clinically important effect size (relative odds of survival at 5 years=1.2) that challenges the current therapeutic paradigm.”

The VMMC Quality Equation

$$Q = A \times \frac{(O + S)}{W}$$

Q: Quality

A: Appropriateness

O: Outcomes

S: Service

W: Waste

The VMMC Quality Equation

$$Q = A \times \frac{(O + S)}{W}$$

Q: Quality
A: Appropriateness
O: Outcomes
S: Service
W: Waste

$$Q = S \times \frac{O + A}{W}$$

$$Q = (A + O) \times S - W$$

$$Q = {}^W \sqrt{A^O + S^O}$$

Parameter	Effect on Quality
Appropriateness	Increase
Outcomes	Increase
Service	Increase
Waste	Decrease

The VMMC Quality Equation

$$Q = A \times \frac{(O + S)}{W}$$

Q: Quality

A: Appropriateness

O: Outcomes

S: Service

W: Waste

What are the units?

Units of **Outcomes** and **Service** have to be the same to add them.

Quality has to be in units of

$$\frac{\text{Appropriateness}}{\text{Waste}} \times \text{whatev.}$$

Mathiness is bullshit


- Disregards logic and factual accuracy.
- Trades on the air of rigor conferred by mathematical equations.
- Aims to impress or persuade an audience, using algebraic shock-and-awe.

What is bullshit?

Bullshit involves language, statistical figures, data graphics, and other forms of presentation intended to impress, overwhelm, or persuade — presented with a blatant disregard for truth, logical coherence, or what information is actually being conveyed.


Example: Sigmund Freud

// So I gave my lecture yesterday. Despite a lack of preparation, I spoke quite well and without hesitation,




Example: Sigmund Freud

// So I gave my lecture yesterday. Despite a lack of preparation, I spoke quite well and without hesitation, which I ascribe to the cocaine I had taken beforehand.




Example: Sigmund Freud



// So I gave my lecture yesterday. Despite a lack of preparation, I spoke quite well and without hesitation, which I ascribe to the cocaine I had taken beforehand.

I told about my discoveries in brain anatomy, all very difficult things that the audience certainly didn't understand


Example: Sigmund Freud



// So I gave my lecture yesterday. Despite a lack of preparation, I spoke quite well and without hesitation, which I ascribe to the cocaine I had taken beforehand.

I told about my discoveries in brain anatomy, all very difficult things that the audience certainly didn't understand, **but all that matters is that they get the impression that I understand it.**"

Example: Sigmund Freud



// So I gave my lecture yesterday. Despite a lack of preparation, I spoke quite well and without hesitation, which I ascribe to the cocaine I had taken beforehand.

Intended to impress, overwhelm, or persuade...presented with a blatant disregard for...what information is actually being conveyed.

I told about my discoveries in brain anatomy, all very difficult things that the audience certainly didn't understand, but all that matters is that they get the impression that I understand it."

Thinking about numbers



Units

% % % %

Percentages



Unfair Comparisons

$$Q = A \times \frac{(O + S)}{W}$$

Mathiness

1...10...100...

Orders of magnitude


Thinking about numbers



Units

% % % %

Percentages



Unfair Comparisons

$$Q = A \times \frac{(O + S)}{W}$$

Mathiness

1...10...100...

Orders of magnitude



38% of Americans wouldn't buy Corona beer "under any circumstances" because of the coronavirus, according to a recent survey.



Phone survey of 737 US beer drinkers
February 25-26th, 2020



- 38% of beer-drinking Americans would not buy Corona under any circumstances now.
- Among those who said they usually drink Corona, only 4% said they would stop drinking Corona, but 14% said they wouldn't order Corona in a public venue
- 16% of beer drinking Americans were confused about whether Corona beer is related to the coronavirus

Thinking about numbers



Units

% % % %

Percentages



Unfair Comparisons


$$Q = A \times \frac{(O + S)}{W}$$

Mathiness

1...10...100...


Orders of magnitude

Disease Deaths per Day Worldwide



sources: Centres for Disease Control, WHO, The Lancet

Disease Deaths per Day Worldwide



sources: Centres for Disease Control, WHO, The Lancet


Thinking about numbers



Units

% % % %

Percentages




Unfair Comparisons

$$Q = A \times \frac{(O + S)}{W}$$

Mathiness

1...10...100...

Orders of magnitude



Think about orders of magnitude
(Fermi Estimation)

Food Stamp Fraud at All-Time High: Is It Time to End the Program?

f share this

✉ email



Dec 27, 2016 // 3:08pm ♥ As seen on Fox & Friends

REACTION: Actress Carrie Fisher Dies at Age 60 After Heart Attack

Should Japanese PM Shinzo Abe Apologize for Pearl Harbor Attack?

Cop Whose House Burned Down Gets Christmas Surprise From Randy Travis <— hasn't

Food stamp fraud is at an all-time high, with cases this year including a state lawmaker and even a millionaire.

According to the USDA, \$70 million of taxpayer money was wasted in 2016 due to food stamp fraud.

\$70 million sounds like a lot of cash.

But how much is it in the context of the entire food stamp program?

What fraction of Americans
receive food stamps?

1%

10%

100%

What fraction of Americans
receive food stamps?

1%

10%

100%

How much does the average food stamp recipient receive annually?

\$100

\$1,000

\$10,000

How much does the average food stamp recipient receive annually?

\$100

\$1,000

\$10,000

How many people are there in the
United States?

How many people are there in the
United States?

About 300,000,000

Thus total expenditures on the food stamp program (not counting administration costs) are about

$$300,000,000 \times 0.1 \times \$1000 =$$

\$30,000,000,000

The fraction lost to fraud is thus

$$\$70,000,000 / \$ 30,000,000,000 =$$

0.2% of expenditures

Typical losses in retail would be
on the order of 1.5% to 3%.

Erik Wemple

Agriculture Department seeks correction from Fox News on food-stamp fraud report

By Erik Wemple December 29, 2016



(screenshot)

Mis/Disinformation

Correlation & causation

Selection bias

Pope Francis Shocks World, Endorses Donald Trump for President, Releases Statement



© 11/01/2016 Fabrica Tedzori Global, Politics 0




VATICAN CITY – News outlets around the world are reporting on the News that Pope Francis has made the unprecedented decision to endorse a US presidential candidate. His statement in support of Donald Trump was released from the Vatican this evening:

"I have been hesitant to offer any kind of support for either candidate in the US presidential election but I now feel that to not voice my concern would be a


dereliction of my duty as the Holy See. A strong and free **America** 🇺🇸 is vitally important in maintaining a strong and free world and in that sense what happens in American elections affects us all. The Rule of **Law** is the backbone of the American government as it is in any nation that strives for freedom and I now fear that the Rule of **Law** in America has been dealt a dangerous blow. The FBI, in refusing to recommend **prosecution** 🚔 after admitting that the law had been broken on multiple occasions by Secretary Clinton, has exposed itself as corrupted by political forces that have become far too powerful.



Data visualization



Big data / ML



Nature of science

Journal view

[illegible]

Of the 50 most shared research studies about health outcomes:

1/3 of journal articles misattribute causality based on correlative evidence

1/2 of news articles do so.



The screenshot shows the PLOS ONE website interface. At the top, the PLOS ONE logo is on the left, and navigation links for 'Publish', 'About', and 'Browse' are on the right. Below the header, there are icons for 'OPEN ACCESS' and 'PEER-REVIEWED', followed by the text 'RESEARCH ARTICLE'. The main title of the article is 'Causal language and strength of inference in academic and media articles shared in social media (CLAIMS): A systematic review'. Below the title, the authors are listed: Noah Haber, Emily R. Smith, Ellen Moscoe, Kathryn Andrews, Robin Audy, Winnie Bell, Alana T. Brennan, Alexander Breskin, Jeremy C. Kane, Mahesh Karra, Elizabeth S. McClure, and Elizabeth A. Suarez, on behalf of the CLAIMS research team. The publication date is May 30, 2018, and the DOI is https://doi.org/10.1371/journal.pone.0196346. At the bottom, there is a horizontal navigation bar with five tabs: 'Article' (highlighted in orange), 'Authors', 'Metrics', 'Comments', and 'Media Coverage'.

PLOS ONE

Publish About Browse

OPEN ACCESS PEER-REVIEWED

RESEARCH ARTICLE

Causal language and strength of inference in academic and media articles shared in social media (CLAIMS): A systematic review

Noah Haber, Emily R. Smith, Ellen Moscoe, Kathryn Andrews, Robin Audy, Winnie Bell, Alana T. Brennan, Alexander Breskin, Jeremy C. Kane, Mahesh Karra, Elizabeth S. McClure, Elizabeth A. Suarez, on behalf of the CLAIMS research team


Published: May 30, 2018 • <https://doi.org/10.1371/journal.pone.0196346>

Article	Authors	Metrics	Comments	Media Coverage
				

Causality and Block Diagrams



Maybe smoking doesn't cause cancer,
maybe cancer causes smoking!



A vintage, sepia-toned photograph of R. A. Fisher. He is an older man with a full white beard and mustache, wearing round-rimmed glasses. He is seated outdoors, leaning forward with his arms crossed over his knees. He is wearing a light-colored, short-sleeved button-down shirt and dark trousers. A pipe is in his mouth, and a plume of smoke is visible rising from it. The background is dark and out of focus, suggesting a wooded or rocky area. The name "R. A. Fisher" is printed in white text on the right side of the image.

R. A. Fisher

CORONAVIRUS | 130,196 views | Jun 6, 2020, 11:26am EDT

Bald Men At Higher Risk Of Severe Coronavirus Symptoms

Marla Milling Contributor ⓘ

Healthcare

I am a Forbes.com Contributor specializing in geriatric health and women's health articles.


Correlation and causation

Baldness



COVID risk

Hypothesis: endocrine involvement in COVID pathogenesis







Fig 2. Possible targets of the androgen pathway for severe acute respiratory syndrome coronavirus 2 (*SARS-CoV-2*) prophylaxis and adjuvant therapy. Antiandrogen therapies include gonadotropin-releasing hormone (*GnRH*) analogs (degarelix, goserelin, leuprolide, leuprorelin, nafarelin), which stop luteinizing hormone (*LH*) secretion and induce chemical castration. Testosterone is regarded as the main androgen hormone, and its production is inhibited by ketoconazole, an inhibitor of steroidogenesis. Dutasteride and finasteride, 5- α -reductase inhibitors, target synthesis of dihydrotestosterone, the most potent intrinsic androgen hormone. Androgen receptor inhibitors may be steroidal (abiraterone, cyproterone, norgestrol, or spironolactone), or nonsteroidal (apalutamide, bicalutamide, darolutamide, enzalutamide, flutamide, or nilutamide). Transmembrane protease, serine 2 (*TMPRSS2*) blockers include bromhexine, camostat, and nafamostat. *ACE*, Angiotensin converting enzyme.

Updated (6/8/20) This piece has been clarified to note that the study did not control for age, which is a risk factor for hair loss and severe Covid-19.



Selection bias occurs when the people who you sample differ systematically from the population at large, with respect to the question you are asking

Ignoring selection bias can produce misleading estimates about a population.





A puzzle from the insurance industry



Switching saves you over
\$500 on average*

Zip Code

Auto



Get a Quote

› Quote with a Local Agent

› Retrieve a Quote

A man with short dark hair, wearing a blue V-neck sweater over a collared shirt, is sitting on a light-colored couch. He has his hands clasped and is looking towards the camera with a slight smile. The background is a bright, out-of-focus interior space.

DRIVERS WHO SWITCHED **SAVED \$498**

Get great protection and a great price, plus an agent!
Quote today and see how much you can save.

FIND AN AGENT

ENTER ZIP

GO

GET A QUOTE

ENTER ZIP

GO

Savings based on new customer-reported data in 2012. Savings vary.
Allstate Fire and Casualty Co. & their affiliates: Northbrook, IL © 2013 Allstate Insurance Co.



Allstate.

New Farmers customers who
purchased multiple policies **saved**
an average of

\$502 each
year



Kirk D. Baldwin

Contact Me



FARMERS



AUTO



HOME



BUSINESS



LIFE



BIG SAVINGS

New GEICO customers report average annual savings over \$500 on car insurance.

Click for a free rate quote. ►►

GEICO

Bull, switch to GEICO and you could save \$500 or more.

To: bullsht.course@gmail.com



3/6/2021: See Why GEICO Could Be Your Best Choice, Bull Shtcourse

Name : Bull Shtcourse

Dear Bull,

There's a high possibility you might be overpaying for your car's insurance. With GEICO's affordable rates and additional discounts, you could bring down your high auto insurance premiums.

Bull, Here's Your Free Quote >>

Selection
bias.




'Mask mouth': Dentists warn prolonged use of masks leading to poor oral hygiene
Dentists are warning about the health issues tied to prolonged use of a mask to stop the spread of the coronavirus.

[🔗 washingtonexaminer.com](https://www.washingtonexaminer.com)

Age of death and musical genre

Average age of death for popular musicians by genre and sex

Average age at death



Life expectancy data from: <http://demog.berkeley.edu/~andrew/1918/figure2.html>




Photo: Clarence Davis

"Murder accounted for 6.0% of deaths across the sample, but was the cause of 51% of deaths in rap musicians and...hip hop musicians, to date. This could be due to these genres' strong associations with drug-related crime and gang culture."

"It's a cautionary tale to some degree. People who go into rap music or hip hop or punk, they're in a much more occupational hazard profession compared to war. We don't lose half our army in a battle."

— Dianna Kenny in the
Washington Post


Photo: Lynn Goldsmith



Age of death and musical genre

Average age of death for popular musicians by genre and sex

Average age at death



Life expectancy data from: <http://demog.berkeley.edu/~andrew/1918/figure2.html>

Right Censoring.


It's not that rap and hip-hop stars are more likely to die young.

It's that they haven't yet had time to die old.




Data visualization

Cumulative iPhone sales



Cumulative iPhone sales






NBC NEWS
NOW


COVID-19 TESTING IN THE U.S.

>1,790,000 tests completed through April 5



THE WHITE HOUSE
WASHINGTON

Cases per 100K▼




Cases per 100K



July 2

Cases per 100K▼




Cases per 100K



July 17

Gun deaths in Florida

Number of murders committed using firearms




Source: Florida Department of Law Enforcement

C. Chan 16/02/2014

REUTERS

Iraq's bloody toll



Hanlon's razor

Never ascribe to malice what can be adequately explained by incompetence.

Never ascribe to incompetence what could be an understandable mistake.


Digital Civics and Ethics



Photo: Carl Bergstrom

Momentous sprint at the 2156 Olympics?

Women sprinters are closing the gap on men and may one day overtake them.



“

Sir — A. J. Tatem and colleagues calculate that women may out-sprint men by the middle of the twenty-second century (*Nature* 431,525; 2004). They omit to mention, however, that (according to their analysis) a far more interesting race should occur in about 2636, when times of less than zero seconds will be recorded.

In the intervening 600 years, the authors may wish to address the obvious challenges raised for both time-keeping and the teaching of basic statistics.”

— Kenneth Rice

Method: *Reductio ad absurdum*




Show that an argument's methods or assumptions lead to ridiculous conclusions.

Photo: Carl Bergstrom





We started with a novel virus and a massive uncertainty vacuum.

We know the entire genomic and molecular structure of the virus



We have used genomic epidemiology to trace its evolution and spread around the globe.



We have
developed 10
COVID vaccines
with more on
the way.

SINO**VAC** *Johnson & Johnson*


BHARAT
BIOTECH

moderna[®]

Sputnik V


AstraZeneca 



SINOPHARM

Pfizer

EpiVax  **CISION**[®]



Misinformation in and about science

Jevin D. West^{a,1}  and Carl T. Bergstrom^b 

^aInformation School, University of Washington, Seattle, WA 98195; and ^bDepartment of Biology, University of Washington, Seattle, WA 98195

Edited by Dietram A. Scheufele, University of Wisconsin–Madison, Madison, WI, and accepted by Editorial Board Member Susan T. Fiske October 11, 2020 (received for review November 15, 2019)

Humans learn about the world by collectively acquiring information, filtering it, and sharing what we know. Misinformation undermines this process. The repercussions are extensive. Without reliable and accurate sources of information, we cannot hope to halt climate change, make reasoned democratic decisions, or control a global pandemic. Most analyses of misinformation focus on popular and social media, but the scientific enterprise faces a parallel set of problems—from hype and hyperbole to publication bias and citation misdirection, predatory publishing, and filter bubbles. In this perspective, we highlight these parallels and discuss future research directions and interventions.

misinformation | disinformation | fake news | data reasoning | science communication

Misinformation has reached crisis proportions. It poses a risk to international peace (1), interferes with democratic decision making (2), endangers the well-being of the planet (3), and threatens public health (4, 5). Public support for policies to control the spread of severe acute respiratory syndrome coronavirus 2 (SARS-CoV-2) is being undercut by misinformation, leading to the World Health Organization’s “infodemic” declaration (6). Ultimately, misinformation undermines collective sense making and collective action. We cannot solve problems of public health, social inequity, or climate change without also addressing the growing problem of misinformation.

Most of the research efforts and interventions examine broad, public consumption of misinformation—modeling the spreading

broadcast media (14), many of these sources are dangerously hyperpartisan.


Nearly 40% of Americans viewed content from untrustworthy websites during the 2016 US election, but these articles only represented about 6% of all news articles consumed (16), and sharing of “fake news” may be less prevalent than often reported in the media (17). That said, even seemingly trustworthy news sites push misleading headlines. Headlines from rival publishers appear side by side on our phones, competing for the ensuing clicks that drive advertising revenue. The unvarnished truth is not always enough to capture our attention. Thorough, detailed, accurate reporting has to compete with clickbait that manufactures emotional responses, curiosity, and anticipation (18). How can thoughtful analysis of minimum wage rates and unemployment trends possibly compete with yet another celebrity breakup, the one hygiene trick your dentist does not want you to know, or nine cats who look like characters from *The Office*? Publishers need flair, fluff, and sparkle to draw our attention—and they have responded enthusiastically.

Nuance falls by the wayside. Headlines often replace factual statements with promises of emotional experiences. Highly shared Facebook headlines pledge to “make you cry tears of joy,” “give you goosebumps,” or “melt your heart” (19). Rather than summarize the contents of the story, headlines deliberately obscure them to incite a click: “How to avoid the leading cause of death”; “Do economists think the Fed will cut rates?” Forward reference headlines (20) exploit our curiosity (21) by including the promise of information with forward reference

Photo: Carl Bergstrom

DATA

Science is
relentlessly
empirical.



Science requires huge volumes of careful data.

"Humans in their natural state are not much disposed to pay attention to such trifles. But they love to win....

[Science] creates a dramatic contest in which the trifles acquire an unnatural luster, becoming, for their tactical worth, objects of fierce desire. [This] redirects great quantities of energy that might have gone to philosophical or other forms of argument into empirical testing."

- Michael Strevens (2020)

Photo: Carl Bergstrom




At its foundation, science has a largely agreed-upon set of data and procedures used to adjudicate disagreements.

Tribal epistemology

“Information is evaluated based not on conformity to common standards of evidence or correspondence to a common understanding of the world, but on whether it supports the tribe’s values and goals and is vouchsafed by tribal leaders. “Good for our side” and “true” begin to blur into one.”


—David Roberts, *Vox*



Center for an Informed Public, Digital Forensic Research Lab, Graphika, & Stanford Internet Observatory (2021). The Long Fuse: Misinformation and the 2020 Election. Stanford Digital Repository: Election Integrity Partnership. v1.2.0 (<https://purl.stanford.edu/tr171zs0069>)



Image: Hubble space telescope



(cc) Image: Environmental Molecular Sciences Lab


Postman's third law: At any given time, the chief source of bullshit with which you have to contend is yourself.

Photo: Carl Bergstrom





Thank you!




@callin_bull



@CT_Bergstrom



@jevinwest



<http://callingbullshit.org>