





Users Meeting – Day 1 Talks Session 4 PIP-II

Lidija Kokoska – PIP-II Project Engineer 53rd Annual Users Meeting August 10, 2020

A Partnership of:

US/DOE

India/DAE

Italy/INFN

UK/UKRI-STFC

France/CEA, CNRS/IN2P3

Poland/WUST



Proton Improvement Plan – II (PIP-II)



"Defining the Decade" with PIP-II


- PIP-II Mission
- PIP-II Recent Highlights
- PIP-II World Class Engagement
- PIP-II Enables new Science



PIP-II MISSION




Present Fermilab accelerator complex & beamlines





PIP-II Accelerator and LBNF Beamline –

capable of >2 MW in the future







P5 Report defines PIP-II Mission



PIP-II will enable the world's most intense beam of neutrinos to the international LBNF/DUNE project, and a broad physics research program, powering new discoveries for decades to come.

PIP-II linac will provide:

Beam Power

- > 1.2 MW proton beam at the start of DUNE
- ➤ Upgradeable to multi-MW capability

Flexibility and multi-user capability


- Compatible with CW-operations
- Customized beams for specific science needs
- ➤ High-power beam to multiple users simultaneously

Reliability

> Fully modernizing the front-end of the Fermilab accelerator complex



PIP-II Scope



800 MeV H- linac

- Warm Front End
- SRF section

Linac-to-Booster transfer line

3-way beam split

Upgraded Booster

- 20 Hz, 800 MeV injection
- New injection area

Upgraded Recycler & Main Injector

RF in both rings

Conventional facilities


- Site preparation
- **Cryoplant Building**
- **Linac Complex**
- **Booster Connection**

The PIP-II scope enables the accelerator complex to reach 1.2 MW proton beam on LBNF target.



10-Aug-2020

PIP-II Superconducting Linac






PIP-II RECENT HIGHLIGHTS



Cryoplant Building Groundbreaking











PIP-II Injector Test Facility (PIP2IT): Systems - Integration Testbed for PIP-II Front End




PIP-II Front-End and Injector Test Facility











PIP2IT Installation Progress





PIP-II WORLD CLASS ENGAGEMENT



PIP-II International Partners, Expertise and Capabilities



India, Department of Atomic Energy (DAE) (started 2009)

BARC, RRCAT, VECC; also IUAC

Substantial engineering/manufacturing experience Superconducting magnets for LHC; 2 GeV synch light source



Italy, INFN (started 2016)

Internationally recognized leader in superconducting RF technologies SRF cavity and cryomodule fabrication for XFEL; SRF cavities for ESS



UK, UKRI (started 2017)

Substantial engineering and manufacturing experience Construction, operation of synch light & neutron sources SRF cavity processing and testing for ESS



France, CEA, CNRS/IN2P3 (started 2017)

Internationally recognized leader in large-scale CM assembly CM assembly for European XFEL and ESS SSR2 cavities and couplers for ESS




Poland, WUST (started 2018)

Substantial engineering and manufacturing experience CDS, LLRF, QC for XFEL and ESS





PIP-II 800 MeV Linac & International Contributions



PIP-II Project benefits from world-leading expertise and capabilities.


No scope gaps.


PIP-II ENABLES NEW SCIENCE




PIP-II Design Is Compatible With Future Science-Driven Upgrades

- PIP-II is designed for >1 MW over 60 120 GeV and 1.2 MW at 120 GeV
- Provides platform for upgrade to >2 MW
- Linac beam power of 1.6 MW (CW), programmable bunch patterns
- Facility enables simultaneous, multi-user, high beam power operations
 - Switch yard to provide beams to Muon Campus in multiuser mode with LBNF
 - Upgrades to mu2e (in conjustion with LBNF/DUNE), truly requires PIP-II's CW capability.
- Linac tunnel includes space and infrastructure to reach 1 GeV
- Tunnel extension (by 120 m) compatible with energy 2–2.5 GeV
- Beam current can be increased by a factor of a few by upgrading amplifiers









PIP-II Major Milestones


- Successfully completed DOE baseline review (2020)
- PIP-II cryogenics plant: Major in-kind contribution awarded
- Cryoplant Building: Planning for August construction start
- Linac Complex final design in progress, complete Dec 2020
- Enable physics by late 2020's












Excellent progress on all fronts: Al/ML

- ✓ PIP-II will utilize transforming potential of Artificial Intelligence and Machine Learning to deliver flexible beam patterns to users quickly, reliably, and with minimal operational effort.
- ✓ Developing AI/ML program for PIP-II and PIP2IT
 - PIP-II: Accelerator Empowered by AI/ML
 - PIP2IT: Testbed for AI/ML Methods
- ✓ Partnering with experts in the field of AI/ML
 - Collaboration with SLAC AI/ML accelerator group
 - Bayesian Optimization (BO) with Gaussian Processes (GP) Model successfully applied to tuning LCLS FEL; gains nearly two orders of magnitude

LCLS Laser Power Tuning Results



- 1. BO with GP 1 minute
- 2. Simplex 5 minutes
- 3. Operator (human) 10's of mins



ARTIFICIAL INTELLIGENCE and MACHINE LEARNING at PIP2IT and PIP-II

